



THE CHALLENGER CASE STUDY



The world has known about many number of accidents. Among them the explosion of the space shuttle "Challenger" is the very familiar one. In those days this case had been reviewed vigorously by media coverage, government reports and transcripts of hearings. This case deals with many ethical issues which engineers faced. It poses many questions before us. What is the exact role of the engineer when safety issues are concern? Who should have the ultimate authority for decision making to order for a launch? Whether the ordering of a launch be an engineering or a managerial decision? Challenger space shuttle was designed to be a reusable one. The shuttle mainly consisted of an orbiter, two solid propellant boosters and a single liquid-propeller booster. All the boosters was ignited and the orbiter was lifted out the earth. The solid rocket booster was of reusable type. The liquid propellant booster was used to finish the lifting of the shuttle in to the orbit. This was only a part of the shuttle which has been reused. The accident took place on 28 th January 1986, due to the failure of one of the solid boosters. In the design of the space shuttle, the main parts which needed careful design of the fields joints where the individual cylinders were placed together.

19GET201/Professional Ethics&Human Values/Unit II/Dr.V.Savitha, AP/CSE





THE CHALLENGER CASE STUDY

The assembly mainly consists of tang and clevis joints which are sealed by two O-rings made up of synthetic rubber only, not specifically hat resistant. The function of the O-rings is to prevent the combustion gases of the solid propellant from escaping. The O-rings were eroded by hot gases, but this was not a serious problem, as the solid rocket boosters were only for reuse initially for the few minutes of the flight. If the erosion of the O-rings could be in a controlled mannaer, and they would not completely burnt through, then the design of the joint would be acceptable, however the design of the O-rings in this shuttle was not so. In the post flight experiment in 1985, the Thiokol engineers noticed black soot and grease on the outside of the boosters due to leak of hot gases blown through the O-rings.

This raised a doubt on the resiliency of the materials used for the O-rings. Thiokol engineers redesigned the rings with steel billets to withstand the hot gases. But unfortunately this new design was not ready by that time of flight in 1986. Before launching, it was necessary to discuss the political environment under which NASA was operating at that time. Because the budget of NASA has decided by Congress. These factors played the main cause for unavoidable delay in the decision to be taken for the shuttle performance, the pressures placed for urgency in launching in 1986 itself, before the launch of RUSSIAN probe to prove to the congress that the program was on processing. The launching date had already been postponed for the availability of vice president GEORGE BUSH, the space NASA supporter. Later further delayed due to a problem in micro switch in the hatch-locking mechanism. The cold weather problem and long discussions went on among the engineers. The number of tele-conferences further delayed the previous testing in 1985 itself. The lowest temperature was 53 F but O-ring temperature during the proposed o

launch period happened to be only 29 F, which was far below the environment temperature _o at which NASA had the previous trail. Somehow, the major factor that made the revised final decision was that previous trial. Somehow, the major factor that made the revised final decision





THE CHALLENGER CASE STUDY

was that with the available data at that time there seemed to be no correlation between the temperature and the degree at which O-rings had eroded by the blow-by gas in the previous launch. Assuming a safety concern due to cold weather, though the data were not concluded satisfactorily, a decision was taken not to delay further for so many reasons, and the launch was finally recommended.

But unexpectedly the overnight temperature at the time of launch was 8 F colder than ^o ever experienced. It was estimated that the temperature of the right hand booster would be only at 28 F. The camera noticed a puff of smoke coming out from the field joints as soon as ^o the boosters were ignited. But the O-rings were not positioned properly on their seats due to extreme cold temperature. The putty used as heat resistant material was also too cold that it failed to protect the O-rings. All these effects made the hot gases to burn past both the Orings, leading to a blowby over an arc around the O-rings. Though immediately further sealing was made by the byproducts of combustion in the rocket propulsion, a glassy oxide formed on the joints. The oxides which were temporarily sealing the field joints at high temperature, later were shattered by the stresses caused by the wind. Again the joints were opened and the hot gases escaped from the solid boosters. But the boosters were attached to the large liquid fuel boosters as per the design. This made the flames due to blow-by from the solid fuel boosters quickly to burn through the external tank. This led to the ignition of the liquid propellant making the shuttle exploded.

Later the accident was reviewed and investigations were carried out by the number of committees involved and by various government bodies. President Regan appointed a commission called Rogers Commission which constituted many distinguished scientists and engineers. The eminent scientists in the commission after thorough examination and investigations gave a report on the flexibility of the material and proved that the resiliency of the material was not sufficient and drastically reduced during the cold launch. As the result of





THE CHALLENGER CASE STUDY

commission hearings, a lot of controversial arguments went on among the Thiokol engineers. Thiokol and NASA investigated possible causes of the explosion. Mr.Boisjoly, the main member in the investigation team, accused Thiokol and NASA of intentionally downplaying the problems with the O-rings while looking for the other causes of the accidents. The hot discussions hurted the feelings and status of the headed engineers like Mr.Boisjoly, Mr.Curtis and Mr.Mellicam. Finally the management's atmosphere also became intolerable. This event shows the responsibility, functions, morality, duties of the engineers leading to ethical problems.